BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No: EE/YNK/BBMP/E-PMT/20/2017-18 Dated: 23-02-2018

APPROVED TENDER SCHEDULE –'B'

Item No: 16

Name of Work:- Providing necessary arrangements for Gamesha immersion work in ward no 04

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri C HEMA GNANESH	
				Rate	Rate in Words
1	Excavation and removal of silt or silt mixed with sand in slussy condition from canal bed including disposing off the same in spoil bankor on the canal embankment in layers as directed etc., complete withinitial lead upto 50 m and all lifts. MISR 2014-15 Page No 131 item No 51	Cum	250.00	154.32	Rupees One Hundred Fifty Four and Paise Thirty Two Only
2	KSRB 100-1 Loading and unloading ofstone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 130 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance of 4.00 K.M (Item No 17.4 Page 130 (SR 2016-17)	cum	250.00	104.15	Rupees One Hundred Four and Paise Fifteen Only
3	Engaging on Hire Basis Crane including Driver/operator with fuel etc complete (SR 2016-17) Page No XXXXVIII code 1087) Sl No 66	Day	11.00	4199.20	Rupees Four Thousand One Hundred Ninety Nine and Paise Twenty Only
4	Engaging on Hire basis of Tractor 50 HP for Conveying of excavated and removal of Stuff from work spot (SR 2016-17) Page No XXXXVI code 1024)	Day	11.00	2637.10	Rupees Two Thousand Six Hundred Thirty Seven and Paise Ten Only
5	Labour charges to Unskilled Mazdoor Heavy (Page no .LIV)SR 2016-17 sl No 5	Day	286.00	271.77	Rupees Two Hundred Seventy One and Paise Seventy Seven Only
6	Code 0516-Providing Plastic Sheet (Page No xxvi/ I.768 PWD SR 2016-17		5544.00	6.68	Rupees Six and Paise Sixty Eight Only
7	Supply of water through water tanker	Load	200.00	566.89	Rupees Five Hundred Sixty Six and Paise Eighty Nine Only
8	Hire charge for Armless Plastic Chairs	Nos	1100.00	4.09	Rupees Four and Paise Nine Only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri C HEMA GNANESH	
				Rate	Rate in Words
9	Hire charge for wooden Table of size 6ft x2ft	Nos	220.00	15.75	Rupees Fifteen and Paise Seventy Five Only
10	Hire charge for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathedaluminium wire (KPWD SR 2010-11 P.55/I.6 IIIb)	Mtrs	3509.00	9.45	Rupees Nine and Paise Forty Five Only
11	1321 Hire charge of 100 KVA generator including operator, Fuel transportation and Handling charges (PWD SR 2013-14(PXXXX /I.92) code No 132	Hrs	88.00	661.37	Rupees Six Hundred Sixty One and Paise Thirty Seven Only
12	Hire Charges for Shamiyana side wall of 8ft hight (Size 15ftx20ft=300sqft)	Rft	3300.00	2.10	Rupees Two and Paise Ten Only
13	Hire charge for Shamiyana with Necessary Bambo Poles Erection Charges Including transportation (Size 15ftx20ft=300sqft)	Sft	3300.00	5.25	Rupees Five and Paise Twenty Five Only
14	KSRB 15.1.1: Providing **flush pointing** to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.(Page No.113/Item No. 15.1)	Sqm	161.00	107.94	Rupees One Hundred Seven and Paise Ninety Four Only
15	KSRB 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications. Page No. 127/ Item No. 15.74/ PWD SR -2016-17	Sqm	108.80	91.25	Rupees Ninety One and Paise Twenty Five Only

C. Hema Gnanesh

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.